



ENSURE BALUSTRADE/HANDRAIL IS 1.0m HIGH min.

NOTE: BACKERBOARD MIN. 12mm H3.1 PLYWOOD OR 6mm FIBRE CEMENT SECURLY FIXED TO TOP PLATE

POLY CAP MUST ONLY BE GLUED ADHERENT - NO FIXINGS ALLOWED

MIN. 1.5mm STO FLEXYL MESHED WATERPROOFING TO EXTEND 50mm PAST WALL JOINTS

STOARMAT RFP MESHED REINFORCEMENT PLASTER TO COVER STO FLEXYL WATERPROOFING

HANDRAILS FIXED THROUGH STO QUADER BLOCK REQUIRE TIMBER PACKER.

<b>STOTHERM PLASTER SYSTEM</b>	<b>STOTHERM INSULATION PLASTER BALUSTRADE DETAIL</b>	<b>STI-450</b>
		<b>JULY 2010</b>

The information contained in this detail is based on our experience and testing and represents the latest information available at the date of issue. This detail is intended for use by the design professional and users of Sto products to assist in developing specific project details to be used in conjunction with a Sto Specification. We reserve the right to alter or update information at any time without prior notice & it is the responsibility of the specifier and/or the project manager to insure that they have the current Sto details and specifications.