



- STOTHERM CAP FIXED WITH STO ADHESIVE MORTAR
- STOFLEXYL MESHED WATERPROOFING TO PARAPET/BALUSTRADE TOP & 50mm MIN. PAST STOTHERM PANEL JOINT
- STO ADHESIVE MORTAR
- STOTHERM COUNTERSUNK ANCHORS @600 CTRS MAX.
- STOTHERM MASONRY INSULATION PLASTER SYSTEM
- SELECTED STOTHERM PANEL

- SELECTED CONC. BLOCK
- STOTHERM MASONRY INSULATION PLASTER SYSTEM

SCALE 1:5

<b>STO CONCRETE BLOCK</b>	<b>STO CONCRETE BLOCK INSULATION SYSTEM PLASTERED PARAPET/BALUSTRADE DETAIL</b>	<b>STCB 501</b>
		<b>2014</b>

The information contained in this detail is based on our experience and testing and represents the latest information available at the date of issue. This detail is intended for use by the design professional and users of Sto products to assist in developing specific project details to be used in conjunction with a Sto Specification. We reserve the right to alter or update information at any time without prior notice & it is the responsibility of the specifier and/or the project manager to insure that they have the current Sto details and specifications.